



PRE-CAST
CONCRETE PLANK
CAMBERED ALONG
LENGTH OF PLANK

GOLD-FORMED
STEEL STUD FRAMING -
WIND-LOAD WALL
CONNECTION TO
PRE-CAST CONCRETE

CFS WIND-LOAD WALL
MULTI-SLOT TOP TRACK
FASTENED TO PRE-CAST PLANK
WITH CONCRETE SCREWS.

MULTI-SLOT TRACK
SCREWED TO EACH
STUD W/ SINGLE
SCREW. MIN. 19MM
GAP BETWEEN TOP OF
STUD AND TRACK TO
ALLOW FOR PRE-CAST
MEMBER DEFLECTION.

CFS WALL STUDS -
SIZE AND GAUGE AS
PER ENGINEERING.
STUD HEIGHTS VARY
BASED ON PRE-CAST
CAMBER.

P: 1-877-251-6875
F: 1-866-873-0360
INFO@TRUSSES.CA



CFS STUD
FRAMING
WIND LOAD WALL
CONNECTION TO
PRE-CAST PANEL